

ABBEVILLE COUNTY SCHOOL DISTRICT
NEW CONCRETE WALKS AT ABBEVILLE HIGH SCHOOL

ADDENDUM NUMBER 1

Prepared by

ABBEVILLE COUNTY SCHOOL DISTRICT
FACILITIES DEPARTMENT
400 Greenville St.
Abbeville, SC 29620
(864) 459-5428 Ext. 244
FAX (864) 459-8531

PROJECT: NEW CONCRETE WALKS AT ABBEVILLE HIGH SCHOOL

Date of Issue: January 18, 2007

The following items take precedence over the referenced portion of the bidding documents for the above referenced project and in executing a contract shall become a part thereof.

DIVISION 2 – SITEWORK

SECTION 02100 – SITE CLEARING

02050.3 EXCAVATION

3.03 TOPSOIL EXCAVATION

Add the following:

- C. Any excess topsoil shall be distributed on the site by the Contractor as directed by the Owner.

DIVISION 3 – CONCRETE

SECTION 03200 – CONCRETE REINFORCEMENT

3200.2 INSTALLATION:

Add the following:

- B. Reinforcement:
 - 1. Fibermesh reinforcement shall be added to the concrete mix.

PROJECT SITE PLAN NOTES

Add the following:

- 1. Delete NOTE 2.
- 2. Delete NOTE 5.
- 3. Add NOTE 7
Furnish six-inch (6") underground drainpipe. Connect two existing roof drain downspouts and pipe under new sidewalk. Terminate drainpipe in protective box.

ABBEVILLE COUNTY SCHOOL DISTRICT
NEW CONCRETE WALKS AT ABBEVILLE HIGH SCHOOL

4. Add NOTE 8
Sidewalk run beside building will be located 6 feet off corners of building unless other wise directed by Owner.
5. Add NOTE 9
Fibermesh reinforcement shall be added to the concrete mix.

See Revised Site Plan

Add additional section of concrete walk approximately thirty feet (30') in length to base bid in area shown on revised site plan.

END OF ADDENDUM NO. 1